

- 1. All finished lumber shall be 2" x 4" minimum.
- A mastic seal shall be provided, as shown, to prevent sediment laden water escaping untreated beneath silt fence installation.
- 3. Silt fence fabric shall be taut and securely stapled to face of upright supports.
- 4. Nails used to secure boards to pavement shall be 20d x 4" minimum length.
- 5. Application design and materials criteria shall be as stated in the Maryland Standards and Specifications for Soil Erosion and Sediment Control.



SILT FENCE INSTALLATION
ON ASPHALT PAVEMENT